

KANNUR UNIVERSITY
(Planning and Development Branch)
NOTICE INVITING QUOTATIONS

PLD/E3/24582/2019

22.04.2025

Sealed competitive Quotations Superscribed as "Plumbing work from Borewell to Gents and Ladies Hostel, Mangattuparamba Campus, Kannur University " are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur -2 on or before 08.05.2025. at 3pm and the quotations will be opened at 3.30pm on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The contractor shall arrange all material & equipment and should be got approved by the Registrar on recommendations of the Engineer in charge and work shall be executed as per KPWD specifications.
3. The Engineer in Charge shall be Assistant Engineer (Electrical).
4. The Payment will be made the through bank account and no advance payment will be sanctioned.
5. Work shall be completed within 60 days from the date of Agreement.
6. The defect Liability period shall be 18 months from the date of completion of the work and the contractor shall be responsible to maintain all his works till completion.
7. Successful Quotationer shall deposit a sum equivalent to 5% of value of contract as performance Guarantee within the period specified in the Work order.
8. The quotationer, before submitting the quotation for the work shall ensure that, the quotationer visited the Site and satisfied himself about the site conditions for the works (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose
9. The Contractor shall make his own arrangements of Water and Electricity.
10. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
11. Quotation Schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Dr. Anup Kumar Kesavan
DIRECTOR (IQAC) (Registrar in-

charge)

KANNUR UNIVERSITY**QUOTATION SCHEDULE****NAME OF WORK : PLUMBING WORK OF BORE WELL AT GENTS AND LADIES HOSTEL, MANGATTUPARAMBA CAMPUS - KANNUR UNIVERSITY**

SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1		Providing and fixing Unplasticized Polyvinyl Chloride(uPVC) pipes,ASTM D-1785 including all uPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with solvent cement ,trnching,refilling & testing of joints complete as per direction of Engineer in Charge.- External Work (Burried)				
1.1	30	40mm dia SCH 40	metre			
2	250	Providing and fixing Unplasticized Polyvinyl Chloride(uPVC) pipes,ASTM D-1785 including all fittings, fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with solvent cement & testing of joints complete as per direction of Engineer in Charge 40mm dia SCH 40 External work - Exposed on wall.	metre			
3	36	Providing and fixing Unplasticized Polyvinyl Chloride(uPVC) pipes,ASTM D-1785 including all fittings, fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with solvent cement & testing of joints complete as per direction of Engineer in Charge 32mm dia SCH 40. External work - Exposed on wall.	metre			
4		Providing and fixing ball valve (brass) of approved quality of following size. Make: Zoloto/SKS/Cim/Equivalent				
4.1	2	40mm dia	each			

5		Providing, fixing, testing and commissioning of gun metal Horizontal/vertical type non-return valve of approved quality (screwed end). This includes jointing of valves with spun yarn/shellac/holditite etc, testing of joints with min. Pressure of 7kg/cm ² or 1.5times of working pressure which is greater and successfully holding time should be 2hrs. Complete as per direction of Engineer-in-Charge				
5.1	1	40mm vertical	each			
6		Unforeseen				
			Total			
			18 % GST			
			Grand Total			

(Rupeesonly)

Signature :

Name and Address of the quotationer :

Date :